

Region 2 Headquarters 3201 Spurgin Road Missoula, MT 59804-3101 406-542-5500 November 4, 2009

*Governor's Office, Attn: Mike Volesky, PO Box 200801, Helena, MT 59620-0801

Environmental Quality Council, PO Box 201704, Helena, MT 59620-1704

*Dept. of Environmental Quality, PO Box 200901, Helena, MT 59620-0901

*Dept. of Natural Resources & Conservation, POB 201601, Helena, MT 59620-1601

*Montana Fish, Wildlife & Parks:

Website, Commission Secretary, Division Secretaries, Regional Office Managers, Region 2 Information Officer.

*State Historic Preservation Office, PO Box 201202, Helena, MT 59620-1202

*MT State Library, PO BOX 201800, Helena, MT 59620-1800

MT Environmental Information Center, Attn: Jim Jensen, POB 1184, Helena, MT 59624-1184

Montana Wildlife Federation, Attn: Craig Sharpe, POB 1175, Helena, MT 59624-1175

Clearwater Resource Council, Attn: Jon Haufler, PO Box 1471, Seeley Lake, MT 59868-1471

*Region 2 FWP Citizens Advisory Committee

**Blackfoot-Clearwater Citizens Advisory Committee

Missoula County Commissioners, 200 W Broadway, Missoula, MT 59802

Missoula County Weed Supervisor, 2825 Santa Fe Crt, Missoula, MT 59808

Missoula Office of Planning & Grants, 435 Ryman, Missoula, MT 59802

Missoula Rural Initiatives, Attn: Pat O'Herren, 200 W Broadway, Missoula, MT 59802

Missoula Conservation District, 3550 Mullan Rd Ste 106, Missoula, MT 59808-5125

Landowners & Adjacent landowners

*Emailed notification of the availability of the EA

**Mailed a postcard notification of the availability of the EA

Dear Interested Citizen:

Enclosed you will find for your review the Draft Environmental Assessment for a Montana Fish, Wildlife & Parks (FWP) proposal to exchange approximately 19 acres on the Blackfoot-Clearwater Wildlife Management Area (BCWMA) along the corridor of Montana Highway 83 with the Montana Department of Transportation (MDT) for a 53-acre parcel that is adjacent to BCWMA's western boundary. This exchange is necessary for MDT's Clearwater Junction-North Project to widen and realign the right-of-way for Highway 83 in Missoula County between Clearwater Junction and Seeley Lake. If implemented, this action would be in lieu of monetary payment from MDT to FWP for right-of-way acquisition across the WMA.

FWP will hold a public meeting in Seeley Lake on November 9, 2009 at 7:00 P.M. in the conference room at the Seeley Lake Ranger Station (west of Highway 83 at milemarker 17), to discuss the proposed acquisition and take public comment.

This draft EA is available for review in Helena at FWP's Headquarters, the State Library and the Environmental Quality Council. It also may be obtained from the Region 2 FWP Headquarters or viewed on FWP's Internet website at http://fwp.mt.gov ("Recent Public Notices").

Comments on this draft EA must be received no later than 5:00 p.m. on November 19, 2009. Comments should be mailed to FWP at the address above or emailed to jkolbe@mt.gov. If you have questions, please contact Jay Kolbe at 406-677-0162.

As part of the decision making process under MEPA, I expect to issue the Decision Notice for this EA very soon after the end of the comment period. The Montana Fish, Wildlife & Parks Commission has the final decision-making authority for FWP land acquisition proposals, and the Commission will be asked to render its decision on this proposal at its December 10th meeting in Helena. Approval will also be necessary from the Montana Board of Land Commissioners.

Sincerely,

Mack Long

Regional Supervisor

ML/sr

Draft Environmental Assessment

Mitigation Plan for MT Highway 83 Right-of-Way Conveyance on the Blackfoot-Clearwater Wildlife Management Area

November 2009

Prepared by

Montana Fish, Wildlife and Parks Helena, Montana

and the

U.S. Fish and Wildlife Service Division of Wildlife and Sportfish Restoration Denver, Colorado

Table of Contents

Purpose and Need	3
Authority and Regulations	6
Alternatives	7
Proposed Action	7
No Action	7
Other Alternatives Considered But Eliminated	7
Affected Environment	8
Physical Resources	8
Soils and Prime/Unique Farmlands	8
Water	9
Biological Resources	9
Vegetation	9
Wildlife Species	10
Socio-Economic Resources	11
Historic and Cultural	11
Aesthetics and Recreation	12
Resources Issues Considered but Eliminated from Detailed Analysis	12
Air Quality	12
Noise	12
Fisheries	13
Community	13
Taxes and Public Services	13
Environmental Consequences	14
Soils and Prime/Unique Farmlands	14
Water	14
Vegetation	15
Wildlife Species	15
Historic and Cultural	16
Aesthetics and Recreation	16
Cumulative Impacts	16
Public Participation	17
Preparers	19
Appendices	
A. Detailed Maps of the WMA Affected Areas	20
B. Property Map of MDT Owned Property	21

PURPOSE AND NEED FOR ACTION

Montana Fish, Wildlife, and Parks (FWP) proposes to exchange approximately 19-acres on the Blackfoot-Clearwater Wildlife Management Area (BCWMA) along the corridor of State Highway 83 in Missoula County to Montana Department of Transportation (MDT) for a 53-acre parcel that is adjacent to BCWMA's western boundary. This exchange is necessary for MDT's project to widen and realign the right-of-way for Highway 83 between Clearwater Junction and Seeley Lake. If implemented, this action would be in lieu of monetary payment from MDT to FWP for right-of-way acquisition across the WMA for MDT's Clearwater Junction-North project.

This project originally initiated in 2001, when MDT first described its need to correct unsafe, substandard curves, and widen a 13-mile portion of Highway 83 beginning at Clearwater Junction north to Seeley Lake. MDT plans to relocate the highway centerline as much as 25 feet to realign curves, improve line-of-sight distances, and provide sufficient road widths for bicycle traffic on the shoulders of the highway. Realignment along the entire corridor would affect FWP property on the Blackfoot-Clearwater WMA at eight specific points.

MDT's need for more right-of-way in the section between miles 4.1 and 4.5 raised several issues that are unique to that site, and required cooperation with FWP. The site is part of the critical winter range for several hundred white-tailed deer, many of which migrate from summer ranges in the upper Clearwater River drainage. Deer routinely cross the highway to the river and back to the WMA as part of their daily or weekly patterns. The site also lies in a migration corridor many of the area's 1,200 elk annually use to travel from summer ranges west of Highway 83 east to the BCWMA. Many other wildlife species were documented crossing this stretch of Highway 83, either routinely or as part of seasonal movements.

Many tons of soil and rock would have to be removed from the WMA to bring the new right-ofway to highway grade, due to the steep slope along the east side of the existing highway along this stretch. This would remove considerably more surface area of important wildlife habitat than implied by the horizontal distance of the cut because of the sloping nature of the land. In addition, by cutting the new right-of-way down to meet the highway, an impassible cut-slope would be created on the east side of the new highway location, which would cause deer that cross from the west to congregate longer on the highway. To alleviate this, the cut-slope would have to be "laid back" to establish a more gentle grade to accommodate wildlife passage, which in turn would require the removal of even more material and more winter habitat. Although the finished highway would be less winding, it would probably promote higher traffic speeds through the area, and according to MDT would support an anticipated 93% increase in traffic volumes over the next 20 years. Due to higher speeds and more traffic over time, the highway itself would likely become a more serious barrier and hazard not only to wintering deer, but also to associated predators and scavengers, and to wide-ranging species such as elk, black bear, grizzly bear and gray wolf that naturally drift through this area while following topography and drainage features at the landscape scale.

Thus, MDT and FWP both recognized that the impact to the BCWMA extended beyond just the 19 acres directly impacted by the proposed realignment. In 2008, a 53-acre parcel directly southwest of the mile marker 4.1-4.5 stretch, and contiguous with the BCWMA, was placed on

the market by a private party as a potential subdivision. This parcel consists of native fescue prairie and ponderosa pine parkland--high quality ungulate winter range. In addition, it included 1,800 feet of Clearwater River frontage at the point most migrating elk and deer use to travel between summer ranges to the west and the main unit of the BCWMA. If the parcel sold on the private market it would almost certainly have been developed for residential use, causing long-term and significant impacts to the function of the adjacent WMA. MDT proposed to purchase the tract and transfer it to FWP to replace the 19 acres of current FWP land that will be impacted by the realignment project and to mitigate for impacts the project will have on the area's wildlife habitat values. This property exchange would eliminate the possibility that MDT would invoke their right of condemnation for the 19 acres. (See Alternatives for addition discussion.)

Legal descriptions and Location of Properties

BCWMA--FWP Owned Property and Originally Purchased with Wildlife Restoration Funds Missoula County, Montana

Legal Description: T15N, R14W

Area #1 – Section 4 Lot 2 & Section 33 SW1/4, SE1/4 (0.78 acres)

Area #2 – Section 21 SW1/4, SW1/4 & Section 28 NE1/4, NW1/4

(1.35 acres)

Area #3 – Section 21, SW1/4, NW1/4 & NW1/4, NW1/4 (4.95 acres)

Total: 7.08 acres currently specified on MDT design plans

** Current finalized design plans only define first portion of MDT's project. Best estimates for other locations for the second portion are:

Area #4 – Section 17, NW1/4, NE1/4 & NE1/4, NE1/4 (0.75 acres)

Area #5 – Section 9, Lot 3 (0.675 acres)

Area #6 – Section 9, Lot 2 (0.895 acres)

Area #7 - Section 4, Lot 5 & Section 5, Lots 1, 5 and 6 & Section 32, Lot 4 (8.14

acres)

Area #8 – Section 5, Lot 2 & Section 32, Lot 4 (1.12 acres)

Total: 11.58 acres

Grand total estimated acres to be affected by proposed action: 18.66 See *Appendix A* for a location map of the affected areas


MDT-Owned Property proposed for acquisition by FWP

Missoula County, Montana

Legal Description: SE ¼ S17, T15N, R14W, Tract B COS 05922

Total: 52.73 acres

See *Appendix B* for a location map



AUTHORITY AND REGULATIONS

1. FWP

Montana Fish, Wildlife & Parks (FWP) purchased the Blackfoot-Clearwater Wildlife Management Area (WMA) in 1948, under the authority granted in 87-1-209 MCA. This statute also authorizes FWP to "develop, operate, and maintain acquired lands or waters." FWP's authority to manage its lands is subject to rules that may be adopted by the Fish, Wildlife & Parks Commission, as described in 87-1-301 MCA.

The WMA was originally purchased with revenues from sales of Montana hunting licenses, and with Federal Aid in Wildlife Restoration monies (Project W-30-L) under Montana's assent to the federal Pittman-Robertson Act (87-1-709 MCA). Lands directly subject to this proposal were purchased by FWP in 1999 and 2000 from Plum Creek Timber Company with funding enabled by an act of the 1987 Montana Legislature (87-1-241-242 MCA) known as House Bill 526, which earmarked for habitat acquisition a set portion of the revenues generated from sales of Montana Sportsmen's and nonresident Big Game Combination licenses. Management of these lands is subject to guidance provided by the US Fish and Wildlife Service (USFWS) under 87-1-710 MCA, which states that a condition of Montana's assent to the federal Pittman-Robertson Act is that "no license fees paid by hunters in the state of Montana shall be used or taken for any other purpose than the administration and use of the department."

FWP revised its management plan for the Blackfoot-Clearwater WMA in 1989 (dated August 31, 1989). Objectives in the plan are to "manage for the maximum sustainable utilization of the winter range by elk, mule deer and white-tailed deer, with primary emphasis on elk . . ." (within specified environmental and social standards); and to "maximize public access and recreation opportunities [such that] other WMA objectives will not be compromised [and] diverse opportunities for appreciation and enjoyment by the public will be maintained."

FWP may convey an interest in lands it has acquired, if consent is given by the Montana Fish, Wildlife & Parks Commission (87-1-209 MCA). FWP, with the consent of the Commission, may convey lands in its ownership to "other governmental entities" without public notice "if the land is less than 10 acres or the full market value of the interest to be conveyed is less than \$20,000" (87-1-209 MCA). This exchange will also require the approval of the Montana Land Board.

2. US Fish and Wildlife Service

FWP originally purchased the BCWMA in part with Federal Aid in Wildlife Restoration monies (Project W-30-L) that are administered by the US Fish and Wildlife Service. FWP's acceptance of Federal Aid requires the USFWS to oversee proper use of state hunting license dollars under the Pittman-Robertson Act. The lands specifically subject to this proposal were purchased with Federal Aid. FWP has consulted the USFWS on this proposal and received concurrence that the proposed action would adequately replace habitat lost to highway right-of-way acquisition, and would ensure the WMA continues to achieve its intended purpose.

The proposed removal of the Federal interest in the BCWMA tracts constitutes a federal action subject to the provisions of the National Environmental Policy Act of 1969, as amended. USFWS is therefore required to prepare an Environmental Assessment to analyze the effects on

the human environment and document the findings. USFWS will use this Environmental Assessment to determine if the proposed action is likely to result in significant impacts to the human environment. If it is determined that there are no significant adverse impacts, USFWS will issue a Finding of No Significant Impact (FONSI). If it is determined, conversely, that significant impacts might occur, the Service would be required to prepare an Environmental Impact Statement (EIS).

ALTERNATIVES

1. Proposed Action

FWP proposed to exchange approximately 19-acres of the Blackfoot-Clearwater Wildlife Management Area (BCWMA) for 53 acres of Montana Department of Transportation (MDT) owned property to mitigate the wildlife and resource impacts to BCWMA by MDT's project to improve public safety on Highway 83 south of Seeley Lake MT.

The intent of MDT's project is to widen the highway to provide for a wider shoulder that would improve safety and accommodate bicycle traffic. Additionally, MDT's project seeks to improve line-of-sight distances for a number of sections. Their efforts would include the realignment of the highway, which would require new cut and fill slopes along critical sections that will infringe on the WMA.

The property offered by MDT to mitigate resource impacts to the BCWMA is on the west side of Highway 83 adjacent to the WMA. This property has no improvements on it. Habitat is comparable to the habitat found within the WMA (ponderosa pine parks and native grasslands) and would provide access to the Clearwater River and Elbow Lake.

2. No Action

If the No Action alternative were approved, no property exchange would occur between FWP and MDT. For the near future there would be no disturbances to BCWMA. MDT may redesign their plans for the highway corridor's improvement or they may invoke their power of condemnation for matters of ensuring public safety. If the right of condemnation were implemented, FWP would only have the option of receiving monetary compensation for the needed right-of-way on the Blackfoot-Clearwater WMA instead of replacement land that serves a similar function or value. The amount of compensation would be negotiated, based on the appraised value of 19 acres. The 53-acre parcel would likely sell on the open market and be developed for residential use. This would impede wildlife movement to and from the WMA, convert valuable winter range, and create anthropogenic attractants that would threaten the area's bears and other wildlife.

3. Other Alternatives Considered but Eliminated from Further Analysis

During 2002, FWP and MDT considered the construction of wildlife overpass as a way to mitigate the impacts to BCWMA for the highway corridor improvements. As with the current proposal by MDT, the improvements were necessary to decrease the wildlife-vehicle collisions between mile markers 4.1 and 4.5 and to improve public safety in this section of Highway 83. At that time, the cost of the overpass was estimated at \$1.6 million and the proposed mitigation

plan was agreeable to both parties. Since that initial agreement, overpass construction costs have increased to a projected \$6-8 million, which has now made the overpass mitigation option too expensive and unfeasible.

Without the overpass, wildlife are expected to continue to cross the highway corridor at mile marker 4.3, and wildlife-vehicle collisions would continue at the present rate. Over time, wildlife-vehicle collisions are expected to increase, due to increased average traffic speed after the corner is straightened, and due to the predicted 93% increase in traffic volume over the next 20 years.

AFFECTED ENVIRONMENT

The Blackfoot-Clearwater WMA comprises about 65,015 acres in Missoula and Powell counties, with 16,785 acres (26%) in fee-title ownership and the remaining 48,230 acres (74%) included under leases with other state and private landowners or managed under conservation easements held by FWP. It is located near the junction of State Highways 200 and 83 (Clearwater Junction), about 45 miles east of Missoula, Montana. Most WMA lands, as well as those directly subject to this proposal, are located north of Highway 200 within 7 miles of Clearwater Junction. Seeley Lake is the nearest community on Highway 83 (located about 6 miles north of the WMA). Ovando is the nearest community on Highway 200 (located about 6 miles east of the WMA). The wood products, ranching, and recreation/tourism industries support the local economy.

The WMA is situated at the convergence of the Clearwater River and Blackfoot River watersheds, within 2 miles of the rivers confluence. The principal topographic feature of the WMA is Boyd Mountain, which at a peak elevation of 5,625 feet provides a low-lying landform connection with the Swan Range and Bob Marshall Wilderness Area (7 miles north of the WMA), Mission Range and Mission Mountain Wilderness (15 miles northwest of the WMA), and Garnet Range (2 miles south of the WMA). Due to this unique position on the landscape, numerous migratory wildlife species are naturally attracted to the WMA in seasonally high abundance.

1. PHYSICAL RESOURCES

a. Soil and Prime/ Unique Farmland

BCWMA: None of the FWP-owned lands subject to this proposal include Prime or Unique Farmlands based on information from the US Department of Agriculture's Soil Survey Database. Soil types include: gravelly silt loams, rock outcrop complex, gravelly loams, and rubble land complexes.

Area #1 - (0.78 ac.) All Farmland of Statewide Importance

Area #2 – (1.35 ac.) Predominately Farmland of Statewide Importance, small area of Not Prime Farmland

Area #3 – (4.95 ac.) All Farmland of Statewide Importance

Area #4 - (0.75 ac.) Not Prime Farmland

Area #5 - (0.675 ac.) Not Prime Farmland

Area #6 - (0.895 ac.) Not Prime Farmland

Area #7 – (8.14 ac.) Not Prime Farmland
Area #8 – (1.12 ac.) Predominately Not Prime Farmland, small acre of Farmland of
Statewide Importance

MDT-Owned Property: This property does not include any Prime or Unique Farmlands. The majority of the acres are designed as either Farmland of Statewide Importance or Farmland of Local Importance. The soil type for the entire property is gravel loam with slopes of 0-30%.

b. Water Resources

BCWMA: There are no water resources associated with the BCWMA sites identified for the proposed action.

MDT-Owned Property: This property has water rights for a 165' well suitable for domestic use. Additionally, this property includes access to 1,800 feet of river frontage to the Clearwater River, a 0.5-acre pond, and Elbow Lake. This property is not located on a floodplain nor does it include any designated wetlands per USFWS Wetlands database.

2. BIOLOGICAL RESOURCES

a. Vegetation

BCWMA: The subject lands owned by FWP are located on the eastern edge of Highway 83, generally between mile markers 4 and 5. Topography is steeply sloping and generally west facing, with closely interspersed natural benches and small rock-outcroppings. Benches are broader and slopes gradually moderate on the west side of Highway 83, leading 40-160 feet in elevation from the highway to the Clearwater River. Lands on the west side of the highway are part of River Watch Subdivision, a 15-lot subdivision on 50 acres (including a 21-acre "common area"). The area east and west of Highway 83 is forested primarily with Douglas-fir and ponderosa pine. Understory vegetation is grass/shrub, primarily rough fescue, elk sedge, and serviceberry.

Currently, FWP controls noxious weeds on the WMA through mechanical and chemical means per the guidelines of FWP's 2008 Integrated Noxious Weed Management Plan.

Montana Species of Concern

A search of the Montana Natural Heritage Program (MNHP) database disclosed four plant species of concern records on or near the FWP project area.

Species	
Bidens beckii	Beck Water-marigold
Castilleja cervina	Deer Indian Paintbrush
Grindelia howellii	Howell's Gumweed
Nymphaea tetragona	Pygmy Waterlily

MDT-Owned Property: Existing vegetation on the property is a mix of conifers, open grasslands, and riparian shrubs along the Clearwater River. There are no known sensitive species on the property.

b. Wildlife

Annually, between 1,000 and 1,400 elk winter on the BCWMA. In addition, FWP estimates as many as 800 mule deer and 600 white-tailed deer use the area all or part of the year. Data collected from radio-collared animals in the late 1980s and early 1990s indicate that most elk and mule deer in the Clearwater watershed migrate annually to the 35-mi² WMA winter range near Clearwater Junction from an expansive summer-fall range of 750-mi² that includes the southwest corner of the Bob Marshall Wilderness and southeast corner of the Mission Mountain Wilderness. About half of the sample of radio-collared white-tailed deer migrated up to 25 miles from summer ranges in the upper Clearwater River and middle Monture Creek drainages, and the other half were generally resident on and near the WMA.

The Blackfoot-Clearwater area is winter habitat for 20-40 bald eagles. Likewise, it is nesting habitat for several bald eagle pairs that winter in the lower Columbia basin. Grizzly bears are commonly observed on the BCWMA; the area is especially heavily used by grizzlies immediately post-emergence and during fall. Wolves are also routinely seen on the property and established packs occur both immediately east and west of the property. Canada lynx, wolverine, and marten occur on the WMA, as do black bears, moose, mountain lions, and 200 other documented wildlife species.

The FWP and MDT lands subject to this proposal lie within the principal winter concentration area for white-tailed deer on the WMA; it is important for white-tailed deer in mid-late winter as snow depths increase. Elk and mule deer routinely also occupy or cross the highway between the 4 and 5 mile markers. Predators and scavengers associated with wintering white-tailed deer concentrate in this area, including coyote, bald eagle, raven, mountain lion, and gray wolf. Lands within the WMA that are located generally east of Highway 83 and south of Woodworth Road (owned by FWP and the Montana Department of Natural Resources and Conservation) are closed to all public entry from November 11 to May 14 annually to provide elk and deer with undisturbed winter habitat.

Thirty-three mammalian species have been documented on or adjacent to the BCWMA. The Montana Bird Distribution Committee (MBDC, 1996) has compiled observations of 163 different bird species within the quarter latilong containing the project lands from 1991 to 1995.

Endangered, Threatened, or Candidate and State Sensitive Species

The Listed Endangered, Threatened, Proposed and Candidate Species in Missoula County as determined by the Montana Ecological Services Field Office are as follows:

MISSOULA COUNTY		
Lynx canadensis	Canada Lynx	LT, PCH
Ursus arctos horribilis	Grizzly Bear	LT
Salvelinus confluentus	Bull Trout	LT, CH
Coccyzus amercanus	Yellow-billed cuckoo	С
Howellia aquatilis	Water Howellia	LT

Grizzly Bear--Grizzlies routinely use the project area and have been observed crossing Highway 83 on or near lands affected by this proposal and in adjacent residential subdivisions.

Canada Lynx--Resent research data suggest the area immediately north of Seeley Lake and this project may support the highest density of lynx in Montana. Telemetry data from that research project and FWP track surveys have both confirmed limited lynx use of the north and east portions of the BCWMA.

Bull Trout--Bull trout are known to occur as common residents and spawners throughout streams and lakes in the Clearwater and Blackfoot watersheds. Migrant adults occur in Salmon Lake and the Clearwater River and bull trout are routinely found in Cottonwood Creek on the BCWMA. The Clearwater River above Rainy Lake and Morrell Creek are both considered core areas for bull trout in the Blackfoot drainage, while the Clearwater River in the project area and Salmon Lake are both listed as nodal habitats.

Water Howellia--The current Montana distribution of this species is thought to be restricted to the Swan River Valley, north of the project area. Though extensive surveys have been conducted in the Clearwater drainage over the years by various agencies, water howellia has never been documented south of the Swan/Clearwater divide. Additionally, no primary potential habitat for this species would be affected by the proposed project.

Montana Species of Concern

A search of the Montana Natural Heritage Program (MNHP) database disclosed ten species of concern record near the project area.

Species	
Gulo gulo	Wolverine
Lynx canadensis	Canada Lynx
Martes pennanti	Fisher
Gavia immer	Common loon
Haliaeetus leucocephalus	Bald eagle
Otus flammeolus	Flammulated owl
Picoides arcticus	Black-backed woodpecker
Oncorhynchus clarki lewisi	Westslope cutthroat trout
Salvelinus confluentus	Bull Trout

3. SOCIO-ECONOMIC RESOURCES

a. <u>Historical and Cultural</u>

BCWMA: In 1989, a cultural resource inventory of affected lands was completed at the request of MDT in preparation of this realignment project. The survey identified only one site, a rock cairn, within the WMA's boundary but outside the MDT's project area.

No other historic or cultural sites are known to occur within the WMA's lands potentially impacted by this proposal. However, MDT does plan to complete another survey prior to any

groundbreaking activities to ensure sensitive sites are not disturbed by their highway improvement project and the results of that survey will be submitted to the Montana's State Historic Preservation Office.

MDT-Owned Property: There are no known cultural or historic resources associated with this parcel based on a file search completed by Montana's State Historic Preservation Office.

b. Aesthetics and Recreation

BCWMA: Portions of this WMA within deer/elk hunting district 282 are open to the public from May 15th through November 10th for a variety of recreational opportunities that include hiking, wildlife viewing, horseback riding, photography, mountain biking, picnicking, and hunting. Hunting opportunities include black bear, waterfowl, elk, and white-tailed and mule deer. The BCWMA is closed during the winter to protect elk and deer during the critical winter season.

The BCWMA encompasses over 65,000 acres of forested mountains and grassland valleys. The portions of the WMA that are identified in this EA to be exchanged are in close proximity to Highway 83 and are not considered prime recreational or hunting areas.

MDT-Owned Property: This property is part of deer/elk hunting district 285 but public recreational access to the property has been restricted in the past. As previously noted, this parcel does have access to the Clearwater River, Elbow Lake, and a small pond. There is an established gravel road to the interior of property from Highway 83. If acquired by FWP through this proposal, the parcel would be managed as part of the BCWMA and open year-round to public recreational access.

4. RESOURCE ISSUES CONSIDERED BUT ELIMINATED FROM DETAILED ANALYSIS

The Montana Environmental Policy Act (MEPA) provides for the identification and elimination from detailed study of issues which are not significant or which have been covered by a prior environmental review, narrowing the discussion of these issues to a brief presentation of why they will not have a significant effect on the physical or human environment or providing a reference to their coverage elsewhere (ARM 12.2.434(d)). While these resources are important, they were either unaffected or mildly affected by the proposed action or the affects could be adequately mitigated.

a. Air Quality

Construction activities may result in minor and temporary deterioration to air quality in the immediate area.

b. Noise

Construction activities will likely result in temporary negative impacts to the ambient noise level in the immediate area of the highway realignment and construction. Nearby wildlife species are expected to move away from the construction area for quieter areas, but most resident wildlife are already accustomed to the normal highway noises.

c. Fisheries

There are no fish species associate with the BCWMA acres identified for the exchange. The MDT owned property does provide access to the Clearwater River and Elbow Lake, both of which both provide habitats for native and non-native species. The Clearwater River supports bluegill, brook trout, brown trout, bull trout, kokanee salmon, largemouth bass, largescale sucker, longnose dace, longnose sucker, mottled sculpin, mountain whitefish, northern pike, northern pike minnow, peamouth, pumpkinseed, pygmy whitefish, rainbow trout, redside shiner, sculpin, westslope cutthroat trout, and yellow perch. Species present in Elbow Lake include brook trout, cutthroat trout, kokanee salmon, largescale sucker, longnose sucker, northern pike, northern pike minnow, pumpkinseed, rainbow trout, and yellow perch.

Angling pressure along the Clearwater River and at Elbow Lake are considered fairly light. State rankings for each location reported in the 2007 Montana Statewide Angling Pressure Report are 192 and 720 respectively. FWP does not anticipate the angling pressure on the bodies of water to measurably increase because no shoreline improvements to increase access at the 53-acre property are planned if the proposed exchange is approved.

d. Community

The Blackfoot-Clearwater Wildlife Management Area (BCWMA) is located near the intersection of State Highways 83 and 200 in Missoula and Powell Counties, Montana. The closest town to the WMA is Seeley Lake, which is 13-miles north of the highway junction and 4-miles north of the WMA's boundary. Highway 83 is one of the main north-south arteries west of the Rocky Mountain front, from its start at the junction with Highway 200 to 105-miles north to the city of Kalispell. Highway 83 travels past numerous lakes, a state park, and the small hamlets of Swan Lake, Condon, and Ferndale.

Minor impacts to the movements of traffic and commerce along Highway 83 are expected if the exchange were approved. With the approval, MDT will likely begin implementation of their realignment plans, which could cause traffic delays and inconveniences for the duration of the improvements.

e. <u>Taxes and Public Services</u>

If the exchange were approved per state statute 87-1-603, FWP would pay Missoula County a sum equal to the amount of taxes, which would be payable on county assessment of the property were it taxable to a private citizen. The change of ownership of these parcels would not affect the property tax revenue submitted to the county.

Under FWP ownership, the proposed additions to the WMA would be subject the management strategies implemented on the rest of the WMA, which prohibits the construction of buildings on the WMA in order preserve the viewshed, wetlands, and wildlife habitat.

ENVIRONMENTAL CONSEQUENCES

In addition to the preparation of this environmental assessment by FWP, MDT is required complete their own project evaluation to meet the requirements for use of Federal Highway Administration funds. Their assessment would describe the mitigation measures MDT intends to implement to decrease resource impacts in the areas affected by the highway improvements.

1. Soil and Prime/ Unique Farmland

Proposed Action

BCWMA: Soils originally part of the BCWMA would likely be removed or manipulated by MDT for the realignment of portions of Highway 83. MDT would follow prescribed design and construction requirements to ensure the public's safety while traveling through the Clearwater Junction – Seeley Lake corridor. These acres will most certainly be lost for wildlife habitat and agricultural uses.

MDT-Owned Property: The 53 acres will be managed by FWP as part of the Blackfoot-Clearwater Wildlife Management Area (BCWMA) and will be maintained to provide winter range for primarily elk, and for white-tailed and mule deer. No soil disturbing activities are planned and the only access to the property would be via the existing road from Highway 83.

No Action

MDT's proposed realignment project of Highway 83 will likely occur sometime in the future. Under this alternative, it is assumed that MDT has used their authority of condemnation to proceed with the highway project. Soil disturbing activities will dramatically affect the acres within the highway's right-of-way. Small portions of the WMA immediately adjacent to the highway will be moved or placed under the path of the new highway and will be lost to wildlife habitat and forage. Within the targeted spots of the WMA, there are no acres designated as Prime/Unique Farmland.

FWP would receive monetary compensation for the value of the WMA acres and the loss of associated resource values. Such funds would be returned to USFWS per the terms of the Pittman-Robertson Wildlife Restoration Program.

2. Water Resources

Proposed Action

BCWMA: There are no water resources associated with the BCWMA sites identified for the proposed property exchange.

MDT-Owned Property: Under the guidance of the BCWMA Management Plan, the public would gain access to the Clearwater River, Elbow Lake, and pond areas that were previously in private ownership and mostly inaccessible. The public would be able to access those bodies of water on foot. No new roads are to be built to those areas in order to preserve the habitat resources. There are no plans to use the well at this time.

No Action

No water resources would be impacted if this alternative were chosen, because there are no water resources associated with the WMA acres identified within MDT's highway improvement project. However, should the MDT parcel be sold and developed, resulting septic systems and bank alterations associated with residential development could affect water quality along the Clearwater River or Elbow Lake.

3. Vegetation

Proposed Action

BCWMA: Vegetation, including mature conifers, within the targeted areas would be removed and likely covered over by gravel and other construction materials so that widening and realignment of the highway meeting required specifications.

MDT-Owned Property: If approved, FWP would implement noxious weed control measures through mechanical and chemical means per the guidelines of FWP's Integrated Noxious Weed Management Plan to maintain and improve the forage for wildlife species. Rough fescue native grasslands and ponderosa pine parks present on the property would be protected and enhanced.

No Action

Under this alternative, MDT moves ahead with their highway project, which would require the removal and manipulation of vegetation within the highway right-of-way in order to accommodate the path of the realignment and widening of the road. Approximately nineteen acres of BCWMA would be directly affected and lost for wildlife habitat. The 53-acre MDT parcel would likely be developed for residential use and native vegetation would be lost or altered.

4. Wildlife

Proposed Action

BCWMA: Up to 18 acres of important white-tailed deer and elk winter range would be impacted by the realignment Highway 83; additional impacts to wildlife habitat and movements beyond the footprint of the project are also anticipated. Increased traffic volumes and speeds resulting from the project may increase wildlife-vehicle collisions over the next 50 years.

MDT-Owned Property: This 53-acre parcel would be transferred to FWP for perpetual management as part of the BCWMA and for the benefit of wildlife. This parcel contains important ungulate winter range and provides critical connectivity between the main unit of the BCWMA and important seasonal wildlife habitats to the west. Residential subdivision would be prohibited, native vegetation communities would be protected and enhanced, and public recreational access would be secured.

No Action

BCWMA: MDT has the authority to condemn these properties and proceed with the highway realignment project should the proposed action not be adopted. Impacts to the area's wildlife resources would be similar to those under the Proposed Action.

MDT-Owned Property: This parcel would likely be sold and developed for residential use. Residential development of the property would alter and remove native grassland winter range and greatly diminish the parcel's value as a wildlife movement corridor. In addition, residential development would increase the presence of anthropogenic food attractants and thus increase the future risk of human-bear conflicts in the area.

5. Historical and Cultural

Proposed Action

Based on results of the cultural and historic resources survey completed in 1989, there are no sensitive sites with the WMA within the path of the highway's realignment or within the MDT owned property; thusly no impacts are anticipated to cultural and historic resources if the land exchange were approved.

No Action

Under this alternative, the recorded rock cairn within the WMA will remain undisturbed even if MDT's highway plans were initiated.

6. Aesthetics and Recreation

Proposed Action

BCWMA: Public recreational users do not heavily use the WMA's identified parcels because of their close proximity to the highway. Similarly, the highway realignment project will not significantly affect the overall area's viewshed or other aesthetic values.

MDT-Owned Property: The property would be open to the public for hiking, hunting, wildlife viewing, and angling and managed under the guidance of the BCWMA Management Plan and other FWP policies. The open space viewshed would be maintained.

No Action

BCWMA: MDT has the authority to condemn these parcels and proceed with the realignment project. Impacts to the current BCWMA parcels would be similar to those under the Proposed Action.

MDT-Owned Property: The parcel would likely be sold and developed for residential use. Recreational access to the property would be permanently prohibited and the open space viewshed along this scenic stretch of Highway 83 would be lost.

CUMULATIVE IMPACTS

Proposed Action

The action alternative provides a method to mitigate the impacts from the realignment of Highway 83 that is adjacent to FWP's Blackfoot-Clearwater Wildlife Management Area, which is an important winter range for elk, white-tailed deer, and mule deer. In addition to being locally critical wintering area for those species, the WMA provides a secure habitat and migration corridor for numerous other mammals and avian species, including grey wolves, grizzly bear, and lynx. The exchange of properties between FWP and MDT will balance the loss

of the WMA's impacted areas with a gain to the WMA of habitat between the highway and Clearwater River with equal resource values.

The improvements to Highway 83 will occur at some point in the future in order to improve public safety along a popular north-south route for tourists, local residents, and commerce. Migration of wildlife across the highway will continue with or without the highway improvements and vehicle-wildlife incidents will persist. Overall wildlife population diversity and densities on the WMA are not expected to dramatically fluctuate following the completion of the highway improvements because habitat (forage, nesting cover, etc.) values will be preserved.

As previously stated, the Highway Department's plans to correct line-of-sight issues and improve public safety of the highway calls for the realignment of the highway's centerline up to 25' in places, which will require the removal of vegetation and soils. Changes to vegetation and soil resources, especially in the realignment section where a portion of a hillside would be cut away, will be irretrievable once the highway improvements are completed. However, those impacts will be in small sections of the entire highway's length.

Direct and cumulative impacts to the MDT owned property are expected to be minimal if the proposed action is approved because FWP would preserve the existing wildlife and habitat values and the property would be managed as part of the BCWMA for the benefit of game and non-game species. Hunting would be allowed on the property, as well as other non-motorized recreation activities, but no public facilities would be developed within its boundaries.

Based on the above assessment that has not identified any significant negative impacts from the proposed action, an EIS is not required and an EA is the appropriate level of review.

No Action

If this alternative were chosen, direct impacts to the WMA's acres within the path of the highway's realignment path would be the same as under the Proposed Action Alternative. FWP would receive monetary compensation for the loss of the WMA's acres, but habitat resources (forage, cover, and migration paths) associated with those acres would be lost to wildlife.

If MDT's prediction of a 93% increase of traffic along Highway 83 over the next 20-years is correct, there is likely to an increase in vehicle-wildlife collisions even with line-of-sight improvements.

PUBLIC PARTICIAPTION

MDT and FWP actively solicited public comment on the original highway realignment project and mitigation proposal in the Seeley Lake area during an informal scoping period that was initiated with a newsletter that appeared in the *Seeley-Swan Pathfinder* newspaper on March 7, 2002. MDT also mailed individual newsletters to potentially affected individuals and organizations in the project area. This initial scoping effort attracted 28 written replies. A second opportunity for public input in advance of this draft EA was offered in the form of a public meeting and open house on July 31, 2002 at the Seeley Lake Elementary School. Roughly 70 people attended, and an additional 22 written replies were generated. In addition, FWP

contributed 2 informational articles on the subject in its weekly column in the *Seeley-Swan Pathfinder*. Copies of the newsletter, newspaper articles, written responses from the public, and a transcript of the public meeting are available upon request.

Numerous thoughtful and helpful issues and concerns were raised. Both MDT and FWP have reviewed all comments that were received. FWP's decision authority in this matter is much narrower than the scope of the comments received. MDT will consider how to incorporate issues that were raised about aesthetics, safety, and engineering into the design of the entire Clearwater Junction-North project.

The current proposed action is different than that originally scoped in 2002. At that time, mitigation for impacts to existing BCWMA lands was to take the form of a wildlife overpass structure to be constructed at the time the highway project was implemented. Construction of the overpass structure is no longer feasible. Therefore, FWP and MDT are proposing to replace impacted FWP properties and mitigate expected impacts wildlife through the acquisition and protection of a 53-acre parcel directly adjacent to the BCWMA. That proposal is described and analyzed in this document.

The public will be notified in the following manners about opportunities to comment on this current EA, the proposed action and alternatives:

- Two public notices in each of these papers: *Missoulian, Independent Record* (Helena), and *Seeley Swan Pathfinder*;
- Public notice on the Fish, Wildlife & Parks web page: http://fwp.mt.gov ("Recent Public Notices"), and
- Copies of this environmental assessment will be distributed to the neighboring landowners and interested parties to ensure their knowledge of the proposed project.

A public meeting has been scheduled in Seeley Lake on November 9th (beginning at 7 p.m.) to coincide with the public comment period. The meeting will be held in the conference room at the Seeley Lake Ranger Station (located west of Highway 83 at mile marker 17).

The public comment period for state purposes will extend for (14) fourteen days from the date when the assessment is published by the FWP website. Written comments to this Draft Environmental Assessment will be accepted until 5 p.m. on November 19, 2009 and can be mailed to the following:

Blackfoot-Clearwater Mitigation Plan EA Montana Fish, Wildlife & Parks 3201 Spurgin Rd. Missoula, MT 59804

Or emailed to jkolbe@mt.gov

EA PREPARATION

Adam Brooks
Federal Aid Program Manager
Montana Fish, Wildlife and Parks
1420 East 6th Ave., Helena MT 59601

<u>abrooks@mt.gov</u> Phone 406-444-3032


Rebecca Cooper MEPA Coordinator Montana Fish, Wildlife and Parks 1420 East 6th Ave., Helena MT 59601 rcooper@mt.gov Phone 406-444-4756

Jay Kolbe WMA Manager & Wildlife Biologist Montana Fish, Wildlife and Parks PO Box 1288, Seeley Lake MT 59868 jkolbe@mt.gov Phone 406-677-0162

Appendices

- A. Portions of the WMA Affected by the MDT Project
- B. Property Map of MDT-Owned Property


Appendix A Portions of the WMA Affected by the MDT Project



Scale 1:80,000

Appendix B

Property Map of MDT-Owned Property (highlighted in yellow)




MT Highway 83 Right-of-Way Conveyance on the Blackfoot-Clearwater Wildlife Management Area

DRAFT MANAGEMENT PLAN

INTRODUCTION

Montana Fish, Wildlife, and Parks (FWP) proposes to exchange up to 19-acres on the Blackfoot-Clearwater Wildlife Management Area (BCWMA) along the Highway 83 corridor to Montana Department of Transportation (MDT) for a 53-acre parcel that is adjacent to BCWMA's western boundary. This exchange is necessary for MDT's project to widen and realign the right-of-way for Highway 83 between Clearwater Junction and Seeley Lake. If implemented, this action would be in lieu of monetary payment from MDT to FWP for right-of-way acquisition across the WMA for MDT's Clearwater Junction-North project.

This project originally initiated in 2001, when MDT first described its need to correct unsafe, substandard curves, and widen a 13-mile portion of Hwy 83 beginning at Clearwater Junction north to Seeley Lake. MDT plans to relocate the highway centerline as much as 25 feet to realign curves, improve line-of-sight distances, and provide sufficient road widths for bicycle traffic on the shoulders of the highway. Realignment along the entire corridor would affect FWP property on the Blackfoot-Clearwater WMA at eight specific points.



MDT and FWP both recognized that the impact to the FWS-encumbered BCWMA lands extended beyond just the 19 acres directly impacted by the proposed realignment. In 2008, a 53-acre parcel directly southwest of the mm 4.1-4.5 stretch, and contiguous with the BCWMA, was placed on the market by a private party as a potential subdivision. This parcel consists of native fescue prairie and ponderosa pine parkland—high quality ungulate winter range. In addition, it included 1,800 feet of Clearwater River frontage at the point most migrating elk and deer use to travel between summer ranges to the west and the main unit of the BCWMA. If the parcel sold on the private market it would almost certainly have been developed for residential use, causing long-term and significant impacts to the function of the adjacent WMA. MDT proposed to purchase the tract and transfer it to FWP to replace the 19 acres of current FWP land that will be impacted by the realignment project and to mitigate for impacts the project will have on the area's wildlife habitat values.

This draft management plan outlines FWP's strategies for meeting the obligations it would accept as part of the cost of acquiring the subject lands. After revising this draft plan to reflect

public review and comment, the final version will serve as an amendment to the existing comprehensive management plan for the BCWMA (revised 1989).

AREA DESCRIPTION

Legal descriptions and Location of Properties

BCWMA - FWP Owned Property and Originally Purchased with Wildlife Restoration Funds Missoula County, Montana

Legal Description: T15N, R14W

Area #1 – Section 4 Lot 2 & Section 33 SW1/4, SE1/4 (0.78 acres)

Area #2 – Section 21 SW1/4, SW1/4 & Section 28 NE1/4, NW1/4

(1.35 acres)

Area #3 – Section 21, SW1/4, NW1/4 & NW1/4, NW1/4 (4.95 acres)

Total: 7.08 acres currently specified on MDT design plans

** Current finalized design plans only define first portion of MDT's project. Best estimates for other locations for the second portion are:

Area #4 – Section 17, NW1/4, NE1/4 & NE1/4, NE1/4 (0.75 acres)

Area #5 – Section 9, Lot 3 (0.675 acres)

Area #6 – Section 9, Lot 2 (0.895 acres)

Area #7 - Section 4, Lot 5 & Section 5, Lots 1, 5 and 6 & Section 32, Lot 4 (8.14 acres)

Area #8 – Section 5, Lot 2 & Section 32, Lot 4 (1.12 acres)

Total: 11.58 acres

Grand total estimated acres to be affected by proposed action: 18.66 See *Appendix A* for a location map of the affected areas

MDT- MDT Owned Property proposed for acquisition by FWP

Missoula County, Montana

Legal Description: SE ¼ S17, T15N, R14W, Tract B COS 05922

Total: 52.73 acres

MDT would acquire up to 8 distinct parcels of FWP land totaling no more than 19 acres. All of these parcels are directly adjacent and parallel to the existing highway corridor. Due to their scattered nature and juxtaposition to the highway, they provide limited direct wildlife habitat value, although the impact of their loss and the resulting highway improvement project extends beyond the actual footprint of the disposed properties.

The FWP acquisition lies between the Clearwater River and the western boundary of the BCWMA. It includes 1,800 feet of Clearwater River frontage and is comprised of native bunchgrass and ponderosa pine parkland. Lesser amounts of Douglas fir and shrub communities exist on the steeper slopes grading toward the river. The parcel is strategically located at one of the few points along the Clearwater south of Salmon Lake where wildlife can freely cross from summer/fall ranges in the Blanchard/Lost Horse Cr. areas and high quality winter range on the BCWMA. The parcel has been platted for residential subdivision and a well and access road are

in place. Montana DNRC owns and administers lands along the southern boundary of the property.

ENCUMBRANCES

Montana Fish, Wildlife & Parks (FWP) purchased the Blackfoot-Clearwater Wildlife Management Area (WMA), including lands to be transferred to MDT under this proposal, in 1948, under the authority granted in 87-1-209 MCA. This statute also authorizes FWP to "develop, operate, and maintain acquired lands or waters." FWP's authority to manage its lands is subject to rules that may be adopted by the Fish, Wildlife & Parks Commission, as described in 87-1-301 MCA.

The WMA was originally purchased with revenues from sales of Montana hunting licenses, and with Federal Aid in Wildlife Restoration monies (Project W-30-L) under Montana's assent to the federal Pittman-Robertson Act (87-1-709 MCA). Lands directly subject to this proposal were purchased by FWP in 1999 and 2000 from Plum Creek Timber Company with funding enabled by an act of the 1987 Montana Legislature (87-1-241-242 MCA) known as House Bill 526, which earmarked for habitat acquisition a set portion of the revenues generated from sales of Montana Sportsmen's and nonresident Big Game Combination licenses. Management of these lands is subject to guidance provided by the U. S. Fish and Wildlife Service under 87-1-710 MCA, which states that a condition of Montana's assent to the federal Pittman-Robertson Act is that "no license fees paid by hunters in the state of Montana shall be used or taken for any other purpose than the administration and use of the department."

FWP may convey an interest in lands it has acquired, if consent is given by the Montana Fish, Wildlife & Parks Commission (87-1-209 MCA). This exchange will also require the approval of the Montana Land Board.

FWP's acceptance of Federal Aid requires the Service to oversee proper use of state hunting license dollars under the Pittman-Robertson Act. The lands specifically subject to this proposal were purchased with Federal Aid. FWP has consulted the Service on this proposal and received concurrence that the proposed action would adequately replace habitat lost to highway right-of-way acquisition, and would ensure the WMA continues to achieve its intended purpose.

The proposed removal of the Federal interest in the BCWMA tracts constitutes a federal action subject to the provisions of the National Environmental Policy Act of 1969, as amended. USFWS is therefore required to prepare an Environmental Assessment to analyze the effects on the human environment and document the findings. USFWS will use this Environmental Assessment to determine if the proposed action is likely to result in significant impacts to the human environment. If it is determined that there are no significant adverse impacts, USFWS will issue a Finding of No Significant Impact (FONSI). If it is determined, conversely, that significant impacts might occur, the Service would be required to prepare an Environmental Impact Statement (EIS).

MANAGEMENT STRATEGIES

The Subject FWP-acquired lands would be managed in a manner consistent with direction provided in the BCWMA comprehensive management plan (revised 1989), noxious weed management plan (1992), plan for entering into cooperative management agreements with private landowners (1996), management plan for the West Slope of Boyd Mountain (856 acres purchased from Plum Creek, 1999), and management plan for the Blackfoot-Clearwater Conservation Easement with DNRC (6,850 acres, 2004).

Specifically, this parcel would be opened to the public for year-round use and enjoyment including hunting, wildlife viewing, and fishing. Management would be focused on maintaining and improving native bunch grass communities through active weed control, as necessary. In addition, forest management objectives will focus on the maintenance of the existing ponderosa pine parkland. This stand is in good condition at present and no active forest management is needed or anticipated in the near term. The riparian corridor along the Clearwater on the subject parcel is in good functional condition; no immediate restoration needs have been identified. In general, FWP management of the BCWMA, including the subject parcel, will target the following objectives:

<u>I:</u> Manage for the maximum sustainable utilization of the winter range by elk, mule deer and white-tailed deer within the following standards:

- ➤ Soil condition and development will be maintained or enhanced;
- Adverse impacts to adjacent landowners will be reduced or mitigated;
- The condition of elk and deer populations will be maintained or enhanced;
- Elk and deer populations will be supported by natural winter forage;
- Adverse impacts on other resources such as fisheries, riparian habitats, water quality, native plant communities, and other animal populations will be avoided or mitigated. Opportunities to enhance these resources will be pursued when compatible with elk and deer management (as time and funding allow).

<u>II:</u> Maximize public access and recreation opportunities within the following standards:

- > Other WMA objectives (i.e., wildlife) will not be compromised;
- Diverse opportunities for appreciation and enjoyment by the public will be maintained.

Public Access:

The subject lands lie within the current boundaries of FWP Hunting District (HD) 285 and would be added to the BCWMA. Subject lands would be open to non-motorized travel yearlong.

- ➤ Overnight camping is allowed. Camps may be maintained on the BCWMA for a maximum of 14 days in any 30-day period.
- > Do not block roads or gates.
- ➤ No removal of firewood from the BCWMA.
- Permits required for groups of over 30 people.

Leave no trace of campfires, hitching rails, shooting targets or other litter.

Livestock grazing:

No livestock grazing is anticipated on the parcel in the near term. A separate EA under MEPA would be prepared at such time as FWP might seriously explore the option of prescribing livestock grazing to benefit wildlife habitat.

Noxious Weed Control:

Considerations for managing risks of public contact with herbicide residues and other environmental issues are addressed in the Noxious Weed Management Plan for the BCWMA (1992). Weeds present on this site include spotted knapweed, St.Johnswort, leafy spurge, cheatgrass, and yellow flag iris. These species occur at trace to medium densities and are largely associated with discrete disturbed areas such as the access road and well site. FWP weed management will focus on broadcast herbicide treatment of these documented infestations, biocontrol releases, and spot treatments of yellow flag iris (in coordination with ongoing Missoula County Weed District efforts along the Clearwater) and spot treatments of identified patches of leafy spurge. FWP and the Missoula County Weed District completed a detailed field weed inspection and developed a weed management plan for the parcel in July, 2009. Prescriptions are consistent with the 1992 BCWMA Noxious Weed Management Plan. This inspection report is appended in full, below.

FWP Land Acquisition - Weed Inspection and Report

COMPLIANCE CHECKLIST FOR SECTION 7-22-2154, MCA

Property Name: <u>MDOT FWP 52-ac. Replacement Parcel, Hwy 83 MM4</u> FWP Region: <u>2</u>
County: Missoula
Date of Property Inspection with County Weed Management District:
County Representative(s): <u>Lindsey Bona, Missoula County Weed District</u>
FWP Staff:Jay Kolbe, FWP Area Wildlife Biologist

Weed Report (please attach weed inspection report or use the space below to describe noxious weeds present on the property, including observations of weed distribution and abundance):

Submitted by L. Bona, Missoula County Weed District:

"This parcel of property consists of rough fescue prairie meadows, open Ponderosa Pine "parks", Clearwater River frontage, and a pothole pond. The weeds present on this site are spotted knapweed, St.Johnswort, leafy spurge, cheatgrass, and yellow flag iris. Spotted knapweed is scattered throughout the property with infestations ranging from trace to medium in density. The rough fescue prairie seems to be competing quite well with the knapweed. Medium densities of

the spotted knapweed occur where roads, wells, and grazing disturbance has occurred. These medium density infestations probably occur on less than 1/4 of the total property. The occurrence of St.Johnswort is at a trace density and occurs on the fringes of disturbances (mostly the roads). Several small patches of leafy spurge (less then 10 feet in diameter) were discovered along an access road into the property from hwy 83. These patches are growing under several large ponderosa pines. Yellow flag iris is present along the banks of the Clearwater River and several patches have been identified growing adjacent to this parcel and have been mapped under the Clearwater Yellow Flag Iris Project."

Weed Management Plan

Submitted by L. Bona, Missoula County Weed District:

"The top priority for this parcel will be the treatment of the satellite leafy spurge infestation. This weed is considered a new invader under the Missoula County Weed District's jurisdiction and requires immediate attention. It will be treated with 1 pint of picloram and 1 quart 2-4D once a year in the spring before seed set for 3 consecutive years. This leafy spurge patch will continue to be monitored beyond the 3-year treatment to assure eradication. Efforts should be taken to protect the rough fescue prairies and treating a buffer around these areas would be the most efficient use of money. Treatment within the prairie area may adversely affect native forb species. Spotted knapweed can be treated with picloram at 1 pint per ac or milestone at 5 to 7 ounce per acre. Spotted knapweed should be treated prior to flower stage. Medium infested spotted knapweed areas that cannot be treated should receive releases of *Cyphocleonus achates*, the spotted knapweed root weevil. St. Johnswort can be spot treated with 2,4D prior to flowering where it is found. Revegetation with a native seed mix is recommended where the medium density stands of spotted knapweed are controlled. The yellow flag iris that is present along the Clearwater River is being controlled through a cooperative project between the Missoula County Weed District, Fish, Wildlife and Parks, Department of Natural Resources, and Department of Agriculture. These infestations will continue to be monitored and managed in accordance with the FWP Intergrated Weed Management Plan as well as the Missoula County Weed District Weed Mangement Plan."

FWP concurs with and will carry out Missoula County Weed District staff recommendation.

County Weed Management District Representative: I have inspected the property, and reviewed the weed situation with a representative of Montana Fish, Wildlife & Parks. I concur with FWP's weed management plan for property, as summarized above.

Signed:	(Lindsey	/ Bona`)
DISIICU	(Linase)	Doma	/